

<div>MERCY CORPS NIGERIA</div> <div>The Proposed Four-Span Reinforced Concrete Bridge at LAU - A Ward, Lau LGA, Taraba State.</div> <div>BILL OF ENGINEERING RATES MEASUREMENT AND EVALUATIONS (BEME) FOR THE SUPPLY OF</div>				<div>SUPPLIER'S NAME</div> <div></div>	
S/N	ITEM DESCRIPTIONS	UNIT	QTY	RATE	TOTAL (NGN.)
Steel Component					
1	528.3mmx208.7mmx13.2mm Universal Beam, 12M length	8	length		-
2	Binding Wire, 25kgs	10	roll		-
3	Y25mm 12m length	40	Lengths		-
4	Y20mm 12m length	80	Lengths		-
5	Y16mm 12m length	180	Lengths		-
6	Y12mm 12m length	250	Lengths		-
7	Y10mm 12m length	123	Lengths		-
8	Bearing pad	10	Nr		-
9	105 x 188x12mm thick stiffener Plate	21	Nr		-
10	Galvanized steel hand rails, 2" diameter	40	m		-
11	M20X650 anchor J Bolt /Nuts and Washers	40	Nr		-
12	Joint sealant/Metal comb	10	Nr		-
13	Thorma Joint Covering	20	nr		-
14	Transportation costs	1	LS		-
SUB-TOTAL FOR STEEL COMPONENTS					-